### NATRAX/PROC/T&D/23/47

#### Dated 05th Oct 2023

# Corrigendum -1

विषय: निविदा संख्या NATRAX/PROC/टी&डी/23/47, के	Sub: corrigendum for "Supplying, installation,	
तहत NATRAX- पीथमपुर (इंदौर के पास), मध्य प्रदेश में	testing and commissioning (SITC) Standard	
"प्रयोगशाला भवन में मानक संदर्भ परीक्षण टायर (SRTT)	Reference Test Tyre (SRTT) storage chamber	
	(Standard Test Chamber) in laboratory building" at	
भंडारण कक्ष ( <i>स्टैंडर्ड टेस्ट चैंबर</i> ) की आपूर्ति, स्थापना, परीक्षण	NATRAX- Pithampur (near Indore), Madhya	
और कमीशनिंग (SITC)" के लिए श्दधिपत्र: प्री बिड मीटिंग	Pradesh under Tender No.	
	NATRAX/PROC/T&D/23/47 Regarding replies to pre bid meeting:	
के उत्तरों के संबंध में:		

The details of the corrigendum are as mentioned below; Date 20th Oct 2023 को प्रातः 15.00 बजे से and 15.00 hrs onwards on 20th Oct 2023 time Replies of 1. It says "D0 Checklist (Tyre Rolling Resistance Machine)" but nowhere on the list does it mention the details of the machine. bid pre queries **Reply: It is typo error.** 2. The roll resistance is typically measured per wheel, not per vehicle. Reply: As per tender (yes per tyre per wheel) Typo not applicable. 3. What would be the maximum engine size and rpm to be placed inside? What is the maximum heat dissipation expected from the sample? **Reply:** As per tender 4. Is there any specified color for the powder coat inside the chamber?

## **Reply:** As per tender

5. What are the acoustic requirements? (it says "optional" in the list)?

## **Reply:** As per tender

6. It says, "There shall not be any joints." Do you think solid is the only option? Or do they accept joint over-plate?

Reply: As per tender, the joint shall not be visible from out side.

7. What would be the ozone level of the air going into the filter? (ambient? or are there any ozone-generating sources inside?)

	Reply: As per tender, there will not be any Ozone Generating Source inside)
8.	AIS-142 Annex G only asks to conduct tests under 25C conditions. It even states, "If measurements at temperatures other than 25 C are unavoidable (only temperatures not less than 20 C or more than 30 C are acceptable)." Humidity is not mentioned anywhere.
	Reply: As per tender, the storage chamber shall have temperature 14 to 30 Deg. Range of Temperature and the Humidity shall be controllable as RH 50% to 25%.
	The ozone level inside the chamber shall not be more than 5PPb.
9.	ASTM C 1136 is "Standard Specification for Flexible, Low Presence Vapor Retarders for Thermal Insulation." And it does not mention anything about ozone levels.
	<b>Reply: As per tender</b> , please refer ASTM E 1136 cl No. 11 & ASTM F 2493 cl no. 11.

Note: This letter and its annexure shall be part of tender documents

With regards

Head Procurement & Stores For NATRAX